SUPER LINE SET WALL DUCT KIT

PARTS & ACCESSOR

ALL YOU NEED TO MAKE AN INSTALLATION LOOK GREAT.

FOR MINI-SPLITS

SUPER LINE SET WALL DUCT KIT

PART NO	DESCRIPTION	NO. PIECES IN KIT	SIZE	
SEC110	90° Degree Horizontal Elbow	1	4 5/8" DIAMETER	
SWW110	Wall Inlet	1	7 7/8" DIAMETER	
SJ110	Joint	2	4 5/8" DIAMETER	
SDD110	Split Line Tube	3	4" 5/16 DIAMETER	



FLEXIBLE REFRIGERANT LINE SET CONNECTOR

ELIMINATES KINKING OF THE COPPER TUBING WHEN CONNECTING TO THE MINI-SPLIT INDOOR EVAPORATOR 3 FT OVERALL LENGTH.

FLEXIBLE REFRIGERANT LINE SET CONNECTOR

PART NO	DESCRIPTION	LENGTH
SFLC1/4	1/4"	3'
SFLC3/8	3/8"	3'
SFLC1/2	1/2"	3'
SFLC5/8	5/8"	3'

FEATURES:

- 3" copper stubs for silver solder or flaring
- Stainless steel corrugated pipe
- Pressure Rating : 800 PSI suitable for R410a system
- 4 Sizes available

LINE SETS

Table to right shows line set sizerequirements for all of our mini-splits.Standard length available is 15-ft.Optional lengths* are also availableupon request. Any other length needed,please contact us directly.Note: Copper Line Sets.No flare fittings included.



FLEXIBLE REFRIGERANT LINE SET CONNECTOR

PART NO	LIQUID (IN)	SUCTION (IN)	INSULATION (IN)	LENGTH (FT)	OPTIONAL LENGTH (FT)	
LST-A	1/4"	3/8"	1/2"	15'	25'	100'
LST-B	1/4"	1/2"	1/2"	15'	25'	100'
LST-C	1/4"	5/8"	1/2"	15'	25'	100'
LST-D	3/8"	5/8"	1/2"	15'	25'	100'